



ARUP

# Hong Kong West Drainage Tunnel “Four Years of Challenges”

Norwegian Tunnelling Society  
4 November 2019

The background of the slide is a wide-angle photograph of the Hong Kong skyline, showing numerous skyscrapers and buildings along the waterfront, with hills in the background.

**BOUYGUES**  
TRAVAUX PUBLICS

# Content

1. Project Background and Design
2. Western Portal, Eastern Portal and Main Tunnel
3. Adits
4. Dropshafts
5. Q&A

# Flooding Problem on Northern Low-lying Areas



**1992 - Admiralty**



**2005 – Eastern Street**




**2005 – Connaught Road West**




**2008 - Sheung Wan  
after Black Storm Signal**

# Interception Approach









|                            |                                    |
|----------------------------|------------------------------------|
| <b>Main Tunnel Length</b>  | 10.5 km (West 6.6 km, East 3.9 km) |
| <b>Tunnel Internal Dia</b> | 6.25m to 7.25m                     |
| <b>Intake</b>              | 34 nos.                            |
| <b>Dropshaft</b>           | 32 nos. Max 175m deep              |
| <b>Adits</b>               | About 8 km                         |





|  |  |
|--|--|
| <b>Contract Title</b>                  | <b>Contract No. DC/2007/10 –<br/>Design and Construction of Hong Kong West<br/>Drainage Tunnel</b> |
| <b>Client</b>                          | <b>Drainage Services Department / Project<br/>Management Division, HKSAR</b>                       |
| <b>Nature of Construction Contract</b> | <b>Design and Build</b>  |
| <b>Client's Design Consultant</b>      | <b>Ove Arup &amp; Partners Hong Kong Ltd</b>   |
| <b>Contractor</b>                      | <b>Dragages - Nishimatsu Joint Venture (DNJV)</b>  |
| <b>Contractor's Designer</b>           | <b>AECOM Asia Co. Ltd</b>  |
| <b>Original Contract Estimate</b>      | <b>HK\$ 2.75 Billion</b>   |
| <b>Contract Commencement Date</b>      | <b>30 November 2007</b>  |
| <b>Target Completion Date</b>          | <b>2012</b>  |





**West TBM Tunnel:**

- 6.6km in length
- Total volume of excavated material ~ 360,000m<sup>3</sup>
- Excavation Duration – 21.5 months

**East TBM Tunnel:**

- 3.9km in length
- Total volume of excavated material ~ 165,000m<sup>3</sup>
- Excavation Duration – 16 months

**Adit Tunnels:**


- 32 nos of Adits
- Total 7.9km in length
- ~3m excavation diameter, 2.3 to 3.5m completed diameter
- Total volume of excavated material ~ 60,000m<sup>3</sup>
- Excavation Duration – 24 months

**Drop Shafts:**

- 23 shafts totaling 2200m in depth excavated by RBM
- 2 constructed by RCD method
- 7 excavated by mechanical methods





# Overview of the site geology (Geological Map of Hong Kong)







# Longitudinal Section 1 of 3 (EP to Ch.5+000)




## Longitudinal Section 2 of 3 (Ch.5+000 to Ch.9+600)






## Longitudinal Section 3 of 3 (Ch.9+600 to WP)

- Granite and Volcanic Tuffs are in approximately equal proportion
- Metamorphosed Tuffs between Granite / Tuff Contact Zone



**Mount Davis Formation – Coarse Ash Crystal Tuff**




## Major Faults along the Tunnel Alignment




### Eight Major Faults Anticipated (Approximate Chainage)

- |                                    |                                   |
|------------------------------------|-----------------------------------|
| 1) 0+645: Tai Tam Fault            | 5) 5+080: Magazine Gap Fault      |
| 2) 2+130: Wong Lai Chung Gap Fault | 6) 6+570: Victoria Gap Fault      |
| 3) 3+270: Middle Gap Fault         | 7) 8+360 & 8+960: Sandy Bay Fault |
| 4) 4+540: Wanchai Gap Fault        | 8) 10+160: Telegraph Bay Fault    |





# Hydraulic Physical Modelling








**Typical completed intake**





 **Portal:**  
**Western Portal at Cyberport**  
**Eastern Portal at Tai Hang**

**Eastern Portal**




**Western Portal**







## Site Layout at Eastern Portal



CRANES FOR LIGHT DUTY LIFTING




### Major Works

Launching Tunnel Excavation (179ml: D&B)  
Portal Structure & River Channel Structure  
Intake Tunnel and Shaft











## Launching Tunnel






**Intake Tunnel**





## Western Portal TBM Launch Tunnel + Spoil Basin Arrangement




**PLAN**













Western Portal









**Western Portal  
Permanent Structure**

## Stilling Basin at Western Portal



Excavation



Completed Stilling Basin







## Methods of Construction :

- Two Hard Rock Double Shield TBM
  - Volcanic on West
  - Granite on East
- Launching from both portals
- External Diameters TBM
  - West TBM=8.3m
  - East TBM=7.2m
- Weight = 1,600t (Both TBM)
  - Cutter head = 160t
  - Remaining TBM Shield=530t
- Length= 230m (Both TBM)
- Delivery Date
  - West TBM : February 2009
  - East TBM : March 2009
- Factory in
  - Germany
  - Shanghai
  - Nansha

## TBM Information



# TBM Fabrication, Assembly and Testing in PRC



- Tunnel Boring Machine (TBM)
  - 1 – Front Shied
  - 2 – Cutterhead
  - 3 – Gripper System
  - 4 – Thrust Cylinder
  - 5 – Segment Erector





12 -Feb-2009 - West TBM Arrival  
at West Portal



12 -Feb-2009 - West T  
Unloading Barge in position



18-Feb-2009 Main Bearing  
Installation



26-Feb-2009 – Forward  
Thrusters Testing



06-March-2009 – TBM Naming  
Ceremony



12-March-2008 – Connect Back Units

TBM Assembly from 12 February to 23 March 2009






23 - March - Cutterhead Transport to Site



23-March-2009 – Unloading  
Cutterhead



31-Mar-2009 – Lifting Main Bearing for  
Installation



02-Apr-2009 – Main Bearing in Position



15-Apr-2009 - Cutterhead Installation






29-Apr-2009 – TBM Shield in Start Position  
Start Back Up Assembly

TBM Assembly from 23 March 2009 to 1 June 2009



## PRE EXCAVATION GROUTING



### Inflow Criteria:

- Not greater than 300 litres/minute from any portal
- Not exceeding 0.2 litres/minute/meter of any probe hole ahead of the excavation face and not more than 1 litre/minute from any 5m length

## PRE EXCAVATION GROUTING


|             | Length of treated tunnel (m) | Number of probe cycles | Total length of probes (m) | Number of grout holes | Total length of grout holes (m) | Total volume of grout injected (m <sup>3</sup> ) |
|-------------|------------------------------|------------------------|----------------------------|-----------------------|---------------------------------|--|
| Eastern TBM | 703                          | 103                    | 5,591                      | 101                   | 4,617                           | 331  |
| Western TBM | 1,800                        | 210                    | 12,280                     | 472                   | 24,258                          | 1,438  |

## Summary of Grout Quantities




## PRE EXCAVATION GROUTING


**TBM Excavation Rate (m/day) versus Water Ingress from Initial Probe Hole (L/min/m)**



**TBM Excavation Rate (m/day) versus Grouting Volume per Probing Cycle (m<sup>3</sup>)**




**Grouting Volume per Probing Cycle (m<sup>3</sup>) versus Water Ingress from Initial Probe Hole (L/min/m)**



## Comparison of Water Inflow, Grout Quantities & TBM Excavation Rate

## Tunnel Lining



**Designed for 1:200 Year Flow**





## Storage on Segment Precast in mainland China

**Supplier: Redland**

**Delivery: By Barge from China to Western Portal  
By Truck from Western Portal to Eastern Portal**

**Total Segments casted : 41292 u**

**Segments cast: 504 u per week  
(6 segments per ring)**

**Typical turning radius between 300m to 930m**





## Western TBM Tunnel


- 6.6Km length in 21.5 Months
- 7.25m I.D.
- Start from Western Portal on 23<sup>rd</sup> March 2009
- Breakthrough on 17<sup>th</sup> January 2011




## Eastern TBM Tunnel

- 3.9Km length in 16 Months
- 6.25m I.D.
- Start from Eastern Portal on 1<sup>st</sup> June 2009
- Breakthrough on 6<sup>th</sup> October 2010







**Adits: 32 nos.**

**7.9Km in total length,  
Length 14m to 800m**

**2 Method of Excavation / Mucking out:**

**— On Rails – 9 No.**

**— On Tyre – 23 No.**



## Methods of Construction :

- Adit Tunnel in Horse-Shoe Shape by Drill & Blast Method
- Initial 5m length by Mechanical Excavation
- Micro blast technique used in later adit junctions
- Maximum 12 concurrent blasting faces
- 2 blast cycles per day on longer adits
- Typical 3m pull per blast



**Mechanical Excavation**



**Drilling for Blasting**

## Micro Blasting :

- Carried out for the initial 5m length of adit
- Pull length range between 300mm to 1m
- MIC range from 0.2kg to 1kg
- Custom made blast door



**Preparation for Blasting**



**Custom Blast Door**



## Concurrent Blasting :



**Blast Door**



**Adit Refuge Chamber**




**Explosive Delivery Truck**




**TBM Refuge Chamber**

Concurrent Blasting :









$d$  DIMENSION FROM CONTRACT (FB)

$d^*$  DIMENSION VARIES DEPENDING ON Q VALUE + DRAINED/UNDRAINED SECTION





Adits Typical Section

## Adit Excavation by Drill & Blast Method – Tyre



### STAGE 1 :

#### Drilling



### STAGE 2 :

#### Charging



SECTION 9-9  
SCALE 1:100







## Adit Excavation by Drill & Blast Method – Tyre



After blasting and ventilation

### STAGE 3 : Mucking out





## STAGE 4 :

### Scaling





## STAGE 5 :

### Shotcreting



## STAGE 6 :



### Rockbolting







## Adit Excavation by Drill & Blast Method – Rails



Face Drilling





Explosive charging





Mucking Out & Scaling



Shotcrete



Rock Bolt



## Concreting :

- Permanent Lining by In-situ Casting Method
- Total of 26 sets of formwork
- Total volume of concrete required;
  - ~26000m<sup>3</sup>
- Maximum concrete volume cast per day;
  - East Adit = 220m<sup>3</sup>
  - West Adit = 370m<sup>3</sup>






## Challenges

### Tight Programme

- Up to 4 sets of formworks operating concurrently in individual adit



## Challenges

### Concrete Delivery Logistics

- Delivery distance of up to 7Km
- Multiple delivery points using intake locations



Delivery from WP

Delivery from Intakes

Delivery from EP





Formwork Erection at Stilling Chamber



Typical Lining Formwork



Formwork Erection at Turning Bay



Formwork Erection at Adit / Main Tunnel Junction




Concreting Arrangement



Concrete Delivery

Typical Details of In-Situ Concrete Lining Works

## Construction Sequences







## Site Constraints




## Methods of Construction




**Open Excavation - 7 nos.**  
**2 types of open excavation**



## Methods of Construction




**Reverse Circular Drilling Machine (RCD) - 2 nos. – Diameter = 2.45m / 3.05m**



**Raise Boring Method 23 nos.**

## STAGE 1: PILOT HOLE





VIEW OF DROPSHAFT WITH INTAKE & TUNNEL






# Drop Shafts by RBM

## STAGE 2: EXCAVATION OF DROP SHAFT BY MEANS OF RBM



## STAGE 3: INSTALLATION OF OF TEMPORARY SUPPORT




VIEW OF DROPSHAFT WITH INTAKE & TUNNEL






# Drop Shifts by RBM


## STAGE 4: PREPARATION FOR DROPSHAFT INSTALLATION



VIEW OF DROPSHAFT WITH INTAKE & TUNNEL





TEMPORARY DECKING OVER REAMER  
HOLE AT BASE SLAB LEVEL




TYPICAL CONNECTION FOR DROPSHAFT  
TO STILLING CHAMBER

## FINAL STAGE: INSTALLATION OF PRECAST LINING




## MOVEMENT & LIFTING INSIDE DROPSHAFT

SCALE: 1:100





- Detailed Design (DDA) for precast ring completed
- 4 Types of Precast Concrete Rings:
  - 1.5m Internal Diameter & 3m High
  - 1.5m Internal Diameter & 1.5m High (Loading restriction on Intake roads)
  - 2.3m Internal Diameter & 2m High
  - 2.3m Internal Diameter & 1m High (Loading restriction on Intake roads)



Lay shear shape into centering cone recess at upper face



Blow up shear shape

# Drop Shafts Lining



Install ring clutch to lifting lug



Blow up lifting lug and ring clutch



Ring clutch  
Lifting Lug



## Challenges

### Restrictions at Intakes on Bowen Road

- 5 Ton weight restriction
- Raise Boring Machine dismantled into ~2 Ton Parts
- Special 1m and 1.5m pre-cast lining used
- Concreting delivered using 1m<sup>3</sup> chutes





# Drop Shafts Lining



Dropshaft MB 16 Completed





***THANK YOU***

***Q&A***

**DSD Hong Kong West Drainage Tunnel  
Project Website**

**<http://www.dsd.gov.hk/others/HKWDT>**